



For most current data sheet and other product information, visit www.burr-brown.com

## Single-Supply, Rail-to-Rail Output, CMOS **INSTRUMENTATION AMPLIFIER**

### **FEATURES**

- RAIL-TO-RAIL OUTPUT SWING: Within 10mV
- LOW OFFSET VOLTAGE: ±200µV
- LOW OFFSET DRIFT: ±5µV/°C
- INTERNAL FIXED GAIN = 10V/V OR 50V/V
- SPECIFIED TEMPERATURE RANGE: -55°C to +125°C
- LOW INPUT BIAS CURRENT: 0.2pA
- WIDE BANDWIDTH: 550kHz in G = 10
- HIGH SLEW RATE: 6.5V/µs
- LOW COST
- SO-8 AND TINY MSOP-8 PACKAGES

### APPLICATIONS

- INDUSTRIAL SENSOR AMPLIFIERS Bridge, RTD, Thermocouple, Flow, Position
- MEDICAL EQUIPMENT ECG, EEG, EMG Amplifiers
- DRIVING A/D CONVERTERS
- PCMCIA CARDS
- AUDIO PROCESSING
- COMMUNICATIONS
- TEST EQUIPMENT
- LOW COST AUTOMOTIVE INSTRUMENTATION

### DESCRIPTION


The INA155 is a low-cost CMOS instrumentation amplifier with rail-to-rail output swing optimized for low voltage, single-supply operation.

Wide bandwidth (550kHz in G = 10) and high slew rate (6.5V/µs) make the INA155 suitable for driving sampling A/D converters as well as general purpose and audio applications. Fast settling time allows use with higher speed sensors and transducers and rapid scanning data acquisition systems.

Gain can be set to 10V/V or 50V/V by pin strapping. Gains between these two values can be obtained with the addition of a single resistor. The INA155 is fully specified over the supply range of +2.7 to +5.5V.

The INA155 is available in MSOP-8 and SO-8 surface-mount packages. Both are specified for operation over the temperature range -55°C to 125°C.

Printed in U.S.A. February, 2000



International Airport Industrial Park • Mailing Address: PO Box 11400, Tucson, AZ 85734 • Street Address: 6730 S. Tucson Blvd., Tucson, AZ 85706 • Tel: (520) 746-1111 Twx: 910-952-1111 • Internet: http://www.burr-brown.com/ • Cable: BBRCORP • Telex: 066-6491 • FAX: (520) 889-1510 • Immediate Product Info: (800) 548-6132

PDS-1529B

# SPECIFICATIONS: $V_S = +2.7V$ to +5.5V

Boldface limits apply over the specified temperature range,  $T_A = -40^{\circ}C$  to  $+85^{\circ}C$ 

At  $T_A$  = +25°C,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.

				INA155E II			INA155EA, UA			
DADAMETED	CONDITION		INA155E, U					<u>-</u> -		
PARAMETER		CONDITION	MIN	TYP	MAX	MIN	TYP	MAX	UNITS	
INPUT										
Offset Voltage, RTI	$V_{OS}$	$V_S = +5.0V, V_{CM} = V_S/2$		±0.2	±1		*	*	mV	
Over Temperature					±1.5			*	mV	
	$dV_{OS}/d_{T}$			±5			*		μV/°C	
vs Power Supply	PSRR	$V_S = +2.7V \text{ to } +6V, V_{CM} = 0.2 \bullet V_S$		±50	±200		*	*	μV/V	
Over Temperature					±250			*	μV/V	
vs Time				±0.4			*		μV/mo	
INPUT VOLTAGE RANGE										
Safe Input Voltage			(V-) - 0.5		(V+) + 0.5	*		*	V	
Common-Mode Range <sup>(1)</sup>	$V_{CM}$	$V_{S} = 5.5V$	0.3		5.2(2)	*		*	V	
		V <sub>S</sub> = 2.7V	0.2		2.5(2)	*		*	V	
Common-Mode Rejection Ratio	CMRR	$V_S = 5.5V$ , $0.6V < V_{CM} < 3.7V$ , $G = 10$	92	100		80	*		dB	
Over Temperature			85			79			dB	
		$V_S = 5.5V, 0.6V < V_{CM} < 3.7V, G = 50$	86	90		77	*		dB	
Over Temperature			85			76			dB	
INPUT IMPEDANCE										
Differential				10 <sup>13</sup>    3			*		Ω    pF	
Common-Mode				10 <sup>13</sup>    3			*		Ω    pF	
				10    0			-4-		22    Pi	
INPUT BIAS CURRENT				14	140			34		
Input Bias Current	Ι <sub>Β</sub>			±1 ±1	±10		*	*	pA	
Offset Current	I <sub>os</sub>			±1	±10		*	*	pA	
NOISE, RTI		$R_S = 0\Omega$ , $G = 10 \text{ or } 50$							1	
Voltage Noise: f = 0.1Hz to 10Hz				4.5			*		μV/Vp-p	
Voltage Noise Density: f = 10Hz				260			*		nV/√Hz	
f = 100Hz				99			*		nV/√ <del>Hz</del>	
f = 1kHz				40			*		nV/√Hz	
Current Noise: f = 1kHz				2			*		fA/√Hz	
GAIN			10		50	*		*	V/V	
Gain Equation			G = 1	0 + 400kΩ/(	Ų.		*		V/V	
Gain Error <sup>(3)</sup>		$V_S = 5.5V$ , $V_O = 0.01V$ to 5.49V, $G = 10$		±0.02	±0.1		*	*	%	
vs Temperature				±2	±10		*	*	ppm/°C	
		$V_S = 5.5V$ , $V_O = 0.05V$ to 5.45V, $G = 50$		±0.05	±0.25		*	*	%	
vs Temperature				±15	±30		*	*	ppm/°C	
Nonlinearity		$V_S = 5.5V, G = 10 \text{ or } 50$		±0.005	±0.015		*	*	% of FSR	
Over Temperature					±0.015			*	% of FSR	
OUTPUT										
Voltage Output Swing from Rail		$R_L = 10k\Omega, G_{ERR} < 0.1\%$		5	10		*	*	mV	
Over Temperature					10			*	mV	
Short-Circuit Current		Short Circuit to Ground		±50			*		mA	
Capacitance Load (stable operation)			Se	e Typical Cu	irve		*			
FREQUENCY RESPONSE										
Bandwidth, -3dB	BW	G = 10		550			*		kHz	
		G = 50		110			*		kHz	
Slew Rate	SR			6.5			*		V/μs	
Settling Time: 0.1%	$t_S$	$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		5			*		μs	
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		11			*		μs	
0.01%		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		8			*		μs	
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		15			*		μs	
Overload Recovery		50% Input Overload		0.2			*		μs	
	THD+N		Se	e Typical Cu	ırve		*			
POWER SUPPLY									1	
Specified Voltage Range			+2.7		+5.5	*		*	V	
Operating Voltage Range				+2.5 to +6			*		V	
Quiescent Current		$V_{IN} = 0, I_{O} = 0$		1.7	2.1		*	*	mA	
Over Temperature		$V_{IN}=0,\ I_O=0$			2.6			*	mA	
TEMPERATURE RANGE										
Specified Range			-40		+85	*		*	°C	
Operating Range			-65		+150	*		*	°C	
		I	-65	I	+150	*	I	*	°C	
Storage Range			00					1 .	1	
Thermal Resistance	$ heta_{\sf JA}$		00							
	$ heta_{\sf JA}$		00	150 150			*		°C/W	

<sup>\*</sup> Same as INA155E, U.

NOTES: (1) For further information, refer to typical performance curves on common-mode input range. (2) Operation above (V+) - 1.8V (max) results in reduced common-mode rejection. See discussion and Figure 6 in the text of this data sheet. (3) Does not include error and TCR of additional optional gain-setting resistor in series with  $R_g$ , if used.



# SPECIFICATIONS: $V_S = +2.7V$ to +5.5V

**Boldface** limits apply over the specified temperature range,  $T_A = -55^{\circ}C$  to  $+125^{\circ}C$ 

At  $T_A$  = +25°C,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


			INA155E, U		INA155EA, UA			1	
PARAMETER		CONDITION	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
INPUT									i
Offset Voltage, RTI	Vos	$V_S = +5.0V, V_{CM} = V_S/2$		±0.2	±1		*	*	mV
Over Temperature	00	, om 6			±2			*	mV
	dV <sub>OS</sub> /d <sub>T</sub>			±5			*		μV/°C
vs Power Supply	PSRR	$V_S = +2.7V \text{ to } +6V, V_{CM} = 0.2 \cdot V_S$		±50	±200		*	*	μV/V
Over Temperature		S S S S S S S S S S S S S S S S S S S			±250			*	μV/V
vs Time				±0.4			*		μV/mo
INPUT VOLTAGE RANGE									F
Safe Input Voltage			(V-) - 0.5		(V+) + 0.5	*		*	V
Common-Mode Range <sup>(1)</sup>	$V_{CM}$	V <sub>S</sub> = 5.5V	0.3		5.2 <sup>(2)</sup>	*		*	V
Common-wode Range	v CM	$V_{S} = 3.3V$ $V_{S} = 2.7V$	0.3		2.5 <sup>(2)</sup>	*		*	V
Common-Mode Rejection Ratio	CMDD	$V_S = 2.7 \text{ V}$ $V_S = 5.5 \text{V}, 0.6 \text{V} < V_{CM} < 3.7 \text{V}, G = 10$	92	100	2.5	80	*	~	dB
Over Temperature	CIVIKK	$V_{\rm S} = 5.5  \text{V}, \ 0.6  \text{V} < V_{\rm CM} < 5.7  \text{V}, \ G = 10$	82 82	100		78	~		dB dB
Over remperature		$V_S = 5.5V, 0.6V < V_{CM} < 3.7V, G = 50$	86	90		7 <b>6</b> 77	*		dB dB
<b>2 T</b>		$v_S = 5.5 \text{ v}, 0.6 \text{ v} < v_{CM} < 5.7 \text{ v}, G = 50$		90			*		1
Over Temperature			84			76			dB
INPUT IMPEDANCE				40 !! -					
Differential				10 <sup>13</sup>    3			*		Ω    pF
Common-Mode				1013    3			*		Ω    pF
INPUT BIAS CURRENT									
Input Bias Current	I <sub>B</sub>			±1	±10		*	*	pΑ
Offset Current	Ios			±1	±10		*	*	pА
NOISE, RTI		$R_S = 0\Omega$ , $G = 10 \text{ or } 50$							
Voltage Noise: f = 0.1Hz to 10Hz				4.5			*		μV/Vp-p
Voltage Noise Density: f = 10Hz				260			*		nV/√ <del>Hz</del>
f = 100Hz				99			*		nV/√ <del>Hz</del>
f = 1kHz				40			*		nV/√Hz
Current Noise: f = 1kHz				2			*		fA/√Hz
GAIN			10		50	*		*	V/V
Gain Equation			G = 10	0 + 400kΩ/(1	10kΩ + R <sub>G</sub> )		*		V/V
Gain Error <sup>(3)</sup>		$V_S = 5.5V$ , $V_O = 0.01V$ to 5.49V, $G = 10$		±0.02	±0.1		*	*	%
vs Temperature				±2	±10		*	*	ppm/°C
		$V_S = 5.5V$ , $V_O = 0.05V$ to 5.45V, $G = 50$		±0.05	±0.25		*	*	%
vs Temperature				±15	±30		*	*	ppm/°C
Nonlinearity		V <sub>S</sub> = 5.5V, G = 10 or 50		±0.005	±0.015		*	*	% of FSR
Over Temperature					±0.015			*	% of FSR
OUTPUT									
Voltage Output Swing from Rail		$R_L = 10k\Omega, G_{ERR} < 0.1\%$		5	10		*	*	mV
Over Temperature		E , EM			10			*	mV
Short-Circuit Current		Short Circuit to Ground		±50			*		mA
Capacitance Load (stable operation)			Se	e Typical Cu	irve		*		
FREQUENCY RESPONSE									
Bandwidth, -3dB	BW	G = 10		550			*		kHz
•		G = 50		110			*		kHz
Slew Rate	SR	$V_{S} = 5.5V, C_{L} = 100pF$		6.5			*		V/μs
Settling Time: 0.1%	ts	$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		5			*		μs
	3	$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		11			*		μs
0.01%		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		8			*		μs
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		15			*		μs
Overload Recovery		50% Input Overload		0.2			*		μs
Total Harmonic Distortion + Noise	THD+N		Se	e Typical Cu	irve		*		
POWER SUPPLY									
Specified Voltage Range			+2.7		+5.5	*		*	V
				+2.5 to +6			*		V
Operating Voltage Range		$V_{IN} = 0, I_{O} = 0$		1.7	2.1		*	*	mA
					2.8			*	mA
		$V_{IN} = 0, I_O = 0$							
Quiescent Current Over Temperature		V <sub>IN</sub> = 0, I <sub>O</sub> = 0			-				
Quiescent Current Over Temperature TEMPERATURE RANGE		V <sub>IN</sub> = 0, I <sub>O</sub> = 0	<b>–</b> 55		+125	*		*	°C
Quiescent Current Over Temperature TEMPERATURE RANGE Specified Range		V <sub>IN</sub> = 0, I <sub>O</sub> = 0	-55 -65			*		*	°C
Quiescent Current Over Temperature TEMPERATURE RANGE Specified Range Operating Range		V <sub>IN</sub> = 0, I <sub>O</sub> = 0			+125			1	
Operating Voltage Range Quiescent Current Over Temperature TEMPERATURE RANGE Specified Range Operating Range Storage Range Thermal Resistance	$ heta_{ ext{IA}}$	V <sub>IN</sub> = 0, I <sub>O</sub> = 0	-65		+125 +150	*		*	°C
Quiescent Current Over Temperature TEMPERATURE RANGE Specified Range Operating Range Storage Range	$ heta_{\sf JA}$	V <sub>IN</sub> = 0, I <sub>O</sub> = 0	-65	150	+125 +150	*	*	*	°C

<sup>\*</sup> Same as INA155E, U.

NOTES: (1) For further information, refer to typical performance curves on common-mode input range. (2) Operation above (V+) - 1.8V (max) results in reduced common-mode rejection. See discussion and Figure 6 in the text of this data sheet. (3) Does not include error and TCR of additional optional gain-setting resistor in series with  $R_G$ , if used.



### **PIN CONFIGURATION**



### ABSOLUTE MAXIMUM RATINGS(1)

Supply Voltage, V+ to V	7.5V
Signal Input Terminals, Voltage(2) (V-	-) $-$ 0.5V to (V+) + 0.5V
Current <sup>(2)</sup>	10mA
Output Short-Circuit(3)	Continuous
Operating Temperature	65°C to +150°C
Storage Temperature	65°C to +150°C
Junction Temperature	+150°C
Lead Temperature (soldering, 10s)	+300°C

NOTE: (1) Stresses above these ratings may cause permanent damage. Exposure to absolute maximum conditions for extended periods may degrade device reliability. These are stress ratings only, and functional operation of the device at these or any other conditions beyond those specified is not implied. (2) Input terminals are diode-clamped to the power supply rails. Input signals that can swing more that 0.5V beyond the supply rails should be current limited to 10mA or less. (3) Short circuit to ground.

# ELECTROSTATIC DISCHARGE SENSITIVITY

This integrated circuit can be damaged by ESD. Burr-Brown recommends that all integrated circuits be handled with appropriate precautions. Failure to observe proper handling and installation procedures can cause damage.

ESD damage can range from subtle performance degradation to complete device failure. Precision integrated circuits may be more susceptible to damage because very small parametric changes could cause the device not to meet its published specifications.

### PACKAGE/ORDERING INFORMATION

PRODUCT	PACKAGE	PACKAGE DRAWING NUMBER	SPECIFIED TEMPERATURE RANGE	PACKAGE MARKING	ORDERING NUMBER <sup>(1)</sup>	TRANSPORT MEDIA
INA155U	SO-8	182	-55°C to +125°C	INA155U	INA155U	Rails
"	n n	"	"	"	INA155U/2K5	Tape and Reel
INA155UA	SO-8	182	-55°C to +125°C	INA155UA	INA155UA	Rails
"	n n	"	"	"	INA155UA/2K5	Tape and Reel
INA155E	MSOP-8	337	-55°C to +125°C	A55	INA155E/250	Tape and Reel
"	n n	"	"	"	INA155E/2K5	Tape and Reel
INA155EA	MSOP-8	337	-55°C to +125°C	A55	INA155EA/250	Tape and Reel
"	n n	"	"	"	INA155EA/2K5	Tape and Reel


NOTES: (1) Models with a slash (/) are available only in Tape and Reel in the quantities indicated (e.g., /2K5 indicates 2500 devices per reel). Ordering 2500 pieces of "INA155UA/2K5" will get a single 2500-piece Tape and Reel.


The information provided herein is believed to be reliable; however, BURR-BROWN assumes no responsibility for inaccuracies or omissions. BURR-BROWN assumes no responsibility for the use of this information, and all use of such information shall be entirely at the user's own risk. Prices and specifications are subject to change without notice. No patent rights or licenses to any of the circuits described herein are implied or granted to any third party. BURR-BROWN does not authorize or warrant any BURR-BROWN product for use in life support devices and/or systems.





### TYPICAL PERFORMANCE CURVES


At  $T_A = +25^{\circ}C$ ,  $V_S = 5.5V$ ,  $R_L = 10k\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


















### TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A$  = +25°C,  $V_S$  = 5.5V,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.




















### TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A = +25^{\circ}C$ ,  $V_S = 5.5V$ ,  $R_L = 10k\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


















### TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A$  = +25°C,  $V_S$  = 5.5V,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.













### APPLICATIONS INFORMATION

Figure 1 shows the basic connections required for operation of the INA155. Applications with noisy or high impedance power supplies may require decoupling capacitors close to the device pins as shown.

The output is referred to the output reference terminal, Ref, which is normally set to  $V_S/2$ . This must be a low-impedance connection to ensure good common-mode rejection. A resistance of  $200\Omega$  in series with the Ref pin will cause a typical device to degrade to approximately 80dB CMRR.

In addition, for the G=50 configuration, the connection between pins 1 and 8 must be low-impedance. A connection impedance of  $20\Omega$  can cause a 0.2% shift in gain error.

### **OPERATING VOLTAGE**

The INA155 is fully specified and guaranteed over the supply range +2.7V to +5.5V, with key parameters guaranteed over the temperature range of -55°C to +125°C. Parameters that vary significantly with operating voltages, load conditions or temperature are shown in the Typical Performance Curves.

The INA155 can be operated from either single or dual power supplies. By adjusting the voltage applied to the reference terminal, the input common-mode voltage range and the output range can be adjusted within the bounds shown in the Typical Performance Curves. Figure 2 shows a bridge amplifier circuit operated from a single +5V power supply. The bridge provides a relatively small differential voltage on top of an input common-mode voltage near 2.5V.





FIGURE 1. Basic Connections.



9

FIGURE 2. Single-Supply Bridge Amplifier.

### **SETTING THE GAIN**

Gain of 10 is achieved simply by leaving the two gain pins (1 and 8) open. Gain of 50 is achieved by connecting the gain pins together directly. In the G=10 configuration, the gain error is less than 0.1%. In the G=50 configuration, the gain error is less than 0.25%.

Gain can be set to any value between 10 and 50 by connecting a resistor  $R_G$  between the gain pins according to the following equation:

$$10 + 400k\Omega/(10k\Omega + R_G) \tag{1}$$

This is demonstrated in Figure 1 and is shown with the commonly used gains and resistor  $R_G$  values. However, because the absolute value of internal resistors is not guaranteed, using the INA155 in this configuration will increase the gain error and gain error drift with temperature, as shown in Figure 3.




FIGURE 3. Typical Gain Error and Gain Error Drift with External Resistor.

### **OFFSET TRIMMING**

The INA155 is laser trimmed for low offset voltage. In most applications, no external offset adjustment is required. However, if necessary, the offset can be adjusted by applying a correction voltage to the reference terminal. Figure 4 shows




FIGURE 4. Optional Trimming of Output Offset Voltage.

INA155

an optional circuit for trimming the output offset voltage. The voltage applied to the Ref terminal is added to the output signal. An op amp buffer is used to provide low impedance at the Ref terminal to preserve good commonmode rejection.

### INPUT BIAS CURRENT RETURN

The input impedance of the INA155 is extremely high—approximately  $10^{13}\Omega$ , making it ideal for use with high-impedance sources. However, a path must be provided for the input bias current of both inputs. This input bias current is less than 10pA and is virtually independent of the input voltage.

Input circuitry must provide a path for this input bias current for proper operation. Figure 5 shows various provisions for an input bias current path. Without a bias current path, the inputs will float to a potential that exceeds the commonmode range and the input amplifier will saturate.

If the differential source resistance is low, the bias current return path can be connected to one input (see the thermocouple in Figure 5). With higher source impedance, using two equal resistors provides a balanced input with advantages of lower input offset voltage due to bias current and better high-frequency common-mode rejection.




FIGURE 5. Providing an Input Common-Mode Current Path.

#### INPUT COMMON-MODE RANGE

The input common-mode range of the INA155 for various operating conditions is shown the in Typical Performance Curves. The common-mode input range is limited by the output voltage swing of A1, an internal circuit node. For the G = 10 configuration, output voltage of A1 can be expressed as:

$$V_{OUTA1} = -\frac{1}{9}V_{REF} + (1 + \frac{1}{9}) V_{IN}$$
 (2)

Using this equation given that the output of A1 can swing to within 10mV of either rail, the input common-mode voltage range can be calculated. When the input common-mode range is exceeded (A1's output is saturated), A2 can still be in linear operation and respond to changes in the non-inverting input voltage. However, the output voltage will be invalid.

The common-mode range for the G=50 configuration is included in the Typical Performance Curve, "Input Common-Mode Range vs Output Voltage."

### INPUT RANGE FOR BEST ACCURACY

The internal amplifiers have rail-to-rail input stages, achieved by using complementary n- and p-channel input pairs. The common-mode input voltage determines whether the p-channel or the n-channel input stage is operating. The transition between the input stages is gradual and occurs between (V+) - 1.8V to (V+) - 0.8V. Due to these characteristics operating the INA155 with input voltages within the transition region of (V+) - 1.8V to (V+) - 0.8V results in a shift in input offset voltage and reduced common-mode and power supply rejection performance. Typical patterns of the offset voltage change throughout the input common-mode range are illustrated in Figure 6. The INA155 can be operated below or above the transition region with excellent results. Figure 7 demonstrates the use of the INA155 in a single-supply, high-side current monitor. In this application, the INA155 is operated above the transition region.

### **RAIL-TO-RAIL OUTPUT**

A class AB output stage with common-source transistors is used to achieve rail-to-rail output. For resistive loads greater than  $10k\Omega$ , the output voltage can swing to within a few millivolts of the supply rail while maintaining low gain error. For heavier loads and over temperature, see the typical performance curve "Output Voltage Swing vs Output Current." The INA155's low output impedance at high frequencies makes it suitable for directly driving Capacitive Digital-to-Analog (CDAC) input A/D converters, as shown in Figure 9.

### INPUT PROTECTION

Device inputs are protected by ESD diodes that will conduct if the input voltages exceed the power supplies by more than 500mV. Momentary voltages greater than 500mV beyond the power supply can be tolerated if the current on the input pins is limited to 10mA. This is easily accomplished with input resistors  $R_{LIM}$  as shown in Figure 8. Many input signals are inherently current-limited to less than 10mA, therefore, a limiting resistor is not required.




FIGURE 6. Input Offset Voltage Changes with Common-Mode Voltage.




FIGURE 7. Single-Supply, High-Side Current Monitor.




FIGURE 8. Input Current Protection for Voltages Exceeding the Supply Voltage.




FIGURE 9. INA155 Directly Drives Capacitive-Input, High-Speed A/D Converter.



### **IMPORTANT NOTICE**

Texas Instruments and its subsidiaries (TI) reserve the right to make changes to their products or to discontinue any product or service without notice, and advise customers to obtain the latest version of relevant information to verify, before placing orders, that information being relied on is current and complete. All products are sold subject to the terms and conditions of sale supplied at the time of order acknowledgment, including those pertaining to warranty, patent infringement, and limitation of liability.

TI warrants performance of its semiconductor products to the specifications applicable at the time of sale in accordance with TI's standard warranty. Testing and other quality control techniques are utilized to the extent TI deems necessary to support this warranty. Specific testing of all parameters of each device is not necessarily performed, except those mandated by government requirements.

Customers are responsible for their applications using TI components.

In order to minimize risks associated with the customer's applications, adequate design and operating safeguards must be provided by the customer to minimize inherent or procedural hazards.

TI assumes no liability for applications assistance or customer product design. TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right of TI covering or relating to any combination, machine, or process in which such semiconductor products or services might be or are used. TI's publication of information regarding any third party's products or services does not constitute TI's approval, warranty or endorsement thereof.

Copyright © 2000, Texas Instruments Incorporated